

TENDER NO. 2019-29

ITEMIZED BID – Part A - Watermain and Sanitary Sewer

In accordance with the first paragraph of this Tender, the Contractor hereby offers to complete the work specified for Tender No. 2019-29 for the following unit prices.

Item No.	SPEC No.	Item Description	Estimated Quantity (Unit)	Unit Price \$	Total \$
GENERAL					
1	-	Insurance & Bonding	(LS)		
2	OPSS Muni 100	Mobilization & Demobilization	(LS)		
3	OPSS Muni 805 OPSD 219.110, 219.100, 219.110	Environmental Protection	(LS)		
4	OPSS Muni 706	Traffic Control	(LS)		
5	OPSS Muni 517, 518	Dewatering	(LS)		
Part A - Sub-Total – General					

Note: Tenders are to provide a credit amount of approximately 137 m of 200 mm diameter HDPE DR11 water main that will be supplied by the Town.

Credit amount = \$ _____

Item No.	SPEC No.	Item Description	Estimated Quantity (Unit)	Unit Price \$	Total \$
WATERMAIN WORKS					
6	OPSS Muni 441	Supply and Install temporary watermain	(LS)		
7	OPSS Muni 441, 442, 450, 490, 491, 492, 501 OPSD 802.010, 802.030, 802.031, 1109.011, 1103.01	New 200mm watermain complete including connections. (incl removal and disposal of existing watermain).	446 (m)		
8	OPSS Muni 441, 416, 442, OPSD 1109.011	Excavate and expose existing 559 mm casing, including removing cap and installing new 200 mm HDPE watermain with bracing as specified.	42 (m)		
9	OPSS Muni 401	Daylight to locate existing watermain.	3 Ea.		
10	OPSS Muni 441, 492, 501, 510, 1010 OPSD 1104.010	Remove and replace existing curb stops and connect with new water services (incl removal and disposal of existing services).	3 (ea.)		
11	OPSS Muni, 441, 442, 510	200 mm Dia. Gate Valve and Valve Box	6 (ea.)		
12	OPSS Muni 441, 442, 510 OPSD 1105.010 217.050	Hydrant Set incl. 150 mm Lead, Valve, and Valve Box	3 (ea.)		
13	OPSS Muni 441, 492, 501, 510, 1010, OPSD 1104.010, 1104.020	Water Services and Appurtenances for Travelodge Hotel & Service Centre	1 (ea.)		
14	OPSS Muni 441	Connect to Existing Watermains	1 (ea.)		
Part A - Sub-Total – Watermain					

Item No.	SPEC No.	Item Description	Estimated Quantity (Unit)	Unit Price \$	Total \$
SEWER WORKS - LOW PRESSURE SEWER / FORCEMAIN					
15	OPSS Muni 401, 412, 450, 491, 492, 501	100 mm HDPE forcemain	788 (m)		
16	OPSS Muni 416, 412	Excavate and expose existing 559 mm casing, including removing cap and installing new 100 mm HDPE forcemain with	42 (m)		
17	OPSS Muni 401, 412, 410, 450, 491, 492, 501	Supply and Install New Sanitary Sewer Services	3 (ea.)		
18	OPSS Muni 410	Connect to existing Sanitary MH	1 (ea.)		
19	OPSS Muni 410	Pressure testing	(LS)		
20	OPSS Muni 401, 402, 409, 410, 491, 492, 501	200 mm diameter PVC Sewer	90 (m)		
21	OPSS Muni 410	1200 Maintenance Holes	2 (Ea.)		
22	OPSS Muni 401	Daylight to locate existing sanitary sewer services	2 (Ea.)		
Part A - Sub-Total – Sewer					

Item No.	SPEC No.	Item Description	Estimated Quantity (Unit)	Unit Price \$	Total \$
PROVISIONAL ITEMS**					
23	OPSS Muni 805, OPSD,219.110	Light Duty Silt Barrier Fence	50 (m)		
24	OPSS Muni 805 OPSD,219.180	Straw Bale Flow Check	5 (ea.)		
25		Utility Relocation	(L.S.)	\$10,000.00	\$10,000.00
26	OPSS Muni 311	Miscellaneous Asphalt	300 (m ²)		
27	OPSS Muni 804	Topsoil and Seeding	2000 (m ²)		
28	OPSS 1010	Granular A	25 (tonnes)		
29	OPSS 1010	Granular B	50 (tonnes)		
Part A - Sub-Total – Provisional					

** This work will be done only on approval of the Contract Administrator and may be eliminated from the contract at the Contract Administrator's discretion. No compensation will be made for the removal of these items from the Contract.

Total Part A - General, Watermain, Sewer, Provisional	
HST	
Total Tender Amount	

TENDER NO. 2019-29

ITEMIZED BID – Part B – Watermain Only

In accordance with the first paragraph of this Tender, the Contractor hereby offers to complete the work specified for Tender No. 2019-29 for the following unit prices.

Item No.	SPEC No.	Item Description	Estimated Quantity (Unit)	Unit Price \$	Total \$
GENERAL					
1	-	Insurance & Bonding	(LS)		
2	OPSS Muni 100	Mobilization & Demobilization	(LS)		
3	OPSS Muni 805 OPSD 219.110, 219.100, 219.110	Environmental Protection	(LS)		
4	OPSS Muni 706	Traffic Control	(LS)		
5	OPSS Muni 517, 518	Dewatering	(LS)		
Part B - Sub-Total – General					

Note: Tenders are to provide a credit amount of approximately 137 m of 200 mm diameter HDPE DR11 water main that will be supplied by the Town.

Credit amount = \$ _____

Item No.	SPEC No.	Item Description	Estimated Quantity (Unit)	Unit Price \$	Total \$
WATERMAIN WORKS					
6	OPSS Muni 441	Supply and Install temporary watermain	(LS)		
7	OPSS Muni 441, 442, 450, 490, 491, 492, 501 OPSD 802.010, 802.030, 802.031, 1109.011, 1103.01	New 200mm watermain complete including connections. (incl removal and disposal of existing watermain).	446 (m)		
8	OPSS Muni 441, 416, 442, OPSD 1109.011	Excavate and expose existing 559 mm casing, including removing cap and installing new 200 mm HDPE watermain with bracing as specified.	42 (m)		
9	OPSS Muni 401	Daylight to locate existing watermain.	3 Ea.		
10	OPSS Muni 441, 492, 501, 510, 1010 OPSD 1104.010	Remove and replace existing curb stops and connect with new water services (incl removal and disposal of existing services).	3 (ea.)		
11	OPSS Muni, 441, 442, 510	200 mm Dia. Gate Valve and Valve Box	6 (ea.)		
12	OPSS Muni 441, 442, 510 OPSD 1105.010 217.050	Hydrant Set incl. 150 mm Lead, Valve, and Valve Box	3 (ea.)		
13	OPSS Muni 441, 492, 501, 510, 1010, OPSD 1104.010, 1104.020	Water Services and Appurtenances for Travelodge Hotel & Service Centre	1 (ea.)		
14	OPSS Muni 441	Connect to Existing Watermains	1 (ea.)		
Part B - Sub-Total – Watermain					

Item No.	SPEC No.	Item Description	Estimated Quantity (Unit)	Unit Price \$	Total \$
PROVISIONAL ITEMS**					
23	OPSS Muni 805, OPSD,219.110	Light Duty Silt Barrier Fence	50 (m)		
24	OPSS Muni 805 OPSD,219.180	Straw Bale Flow Check	5 (ea.)		
25		Utility Relocation	(L.S.)	\$10,000.00	\$10,000.00
26	OPSS Muni 311	Miscellaneous Asphalt	300 (m ²)		
27	OPSS Muni 804	Topsoil and Seeding	2000 (m ²)		
28	OPSS 1010	Granular A	25 (tonnes)		
29	OPSS 1010	Granular B	50 (tonnes)		
Part B - Sub-Total – Provisional					

** This work will be done only on approval of the Contract Administrator and may be eliminated from the contract at the Contract Administrator's discretion. No compensation will be made for the removal of these items from the Contract.

Total Part B - General, Watermain, and Provisional	
HST	
Total Tender Amount	