

TENDER NO. 2019-38**ITEMIZED BID**

In accordance with the first paragraph of this Tender, the Contractor hereby offers to complete the work specified for Tender No. 2019-38 for the following unit prices.

Item No.	SPEC No.	Item Description	Estimated Quantity (Unit)	Unit Price \$	Total \$
GENERAL					
1	-	Bonding & Insurance	(LS)		
2	OPSS Muni 100	Mobilization & Demobilization	(LS)		
3	OPSS Muni 805 OPSD 219.110, 219.100	Environmental Protection	(LS)		
4	OPSS Muni 706	Traffic Control	(LS)		
Sub-Total – General					
Item No.	SPEC No.	Item Description	Estimated Quantity (Unit)	Unit Price \$	Total \$
ROAD WORKS					
5	OPSS Muni 206, Muni 510	Removal & Disposal of Existing Surface Treatment	2725 m ²		
6	OPSS Muni 206, Muni 510, 314	Excavation– Base & Subbase	3574 m ³		
7	OPSS Muni 206, Muni 510	Ditching & Ditch Cleanout	414 m		
8	OPSS 407 OPSD 705.010, 400.010	Ditch Inlet Catch Basins – Remove and Replace	2 Ea.		
9	OPSS Muni 421, 501, 1010, 1801, 1840 OPSD 803.030	Culverts – Install New	1 Ea.		
10	OPSS Muni 421, 501,510, 1010, 1801, 1840 OPSD 803.030	Culverts – Remove and Replace	4 Ea.		

11	OPSS Muni 421, 501, 510, 1010, 1840 OPSD 803.030	Culvert – Remove and Reinstall	5 Ea.		
12	–	Macafferi EG-30 Geogrid & Geotextile	3130 m ²		
13	OPSS MUNI 405	Subdrain – Install New	550 m.		
14	OPSS 102, 206, 314, 501, 1010	Reinstatement of Suitable Excavated Material Base and Subbase	2574 m ³		
15	OPSS Muni 180	Disposal of Unsuitable Subbase Material	1000 m ³		
16	OPSS Muni 102, 206, 314, 501, 1010	Imported Granular B Type 2 for Replacement of Unsuitable Material	2200 tonnes		
17	OPSS Muni 102, 206, 314, 501, 1010	Granular A – Road Works	1350 tonnes		
18	OPSD 601.010 OPSS Muni 312	Asphalt Gutter – Install New	65 m		
19	OPSS Muni 1150, 310 OPSS Prov 308	Asphalt – SP 19.0 Base (Road) 60mm	470 tonnes		
20	OPSS Muni 1150, 310 OPSS Prov 308	Asphalt – SP 12.5 Surface (Road) 50mm	390 tonnes		
21	OPSS Muni 1150, 310 OPSS Prov 308	Asphalt – SP 12.5 Surface (Driveways) 50mm	50 tonnes		
22	OPSS Muni 804	Topsoil and Seed	828 m ²		
23	OPSS Muni 206	Excavation - Excavation Beyond Specified Depths (Provisional)	1500 m ³		

24	OPSS Muni 517, 518	Dewatering (Provisional)	Per Day		
Sub-Total – Road Work					

** This work will be done only on approval of the Contract Administrator and may be eliminated from the contract at the Contract Administrator’s discretion. No compensation will be made for the removal of these items from the Contract.

Total Parts General and Road Work	
HST	
Total Tender Amount	